

| No.                    | Items of work                                                                                                                                                                   | Per     | Quantity |
|------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|----------|
| <i>Labour—concl'd.</i> |                                                                                                                                                                                 |         |          |
| 25                     | Unloading cast iron pipe from Railway waggon ...                                                                                                                                | Cwt.    | 267      |
| 26                     | Loading cast iron pipes to carts ...                                                                                                                                            | "       | 267      |
| 27                     | Carting cast iron pipe from station to work site, average lead being $1\frac{1}{2}$ mile. ...                                                                                   | "       | 267      |
| 28                     | Constructing cisterns for valves ...                                                                                                                                            | No.     | 3        |
| 29                     | Earthwork excavation, refilling and tamping<br>1 (2560 x $2\frac{1}{2}$ x $1\frac{1}{2}$ ) gravelly soil 9600<br>1 (1590 x $2\frac{1}{2}$ x $1\frac{1}{2}$ ) gravelly soil 5962 | C.yd.   | 576      |
|                        | Total 15562                                                                                                                                                                     |         |          |
| 30                     | Road metal 2560 x $2\frac{1}{2}$ x 1 = 6400<br>1590 x $2\frac{1}{2}$ x 1 = 3975                                                                                                 | "       | 384      |
|                        | Total 10375                                                                                                                                                                     |         |          |
| 31                     | Removing $2\frac{1}{2}$ " cast iron pipe s.ft. 1590 or 177 pipes at 7/8 cwt. per pipe of 9' length.                                                                             | Cwt.    | 155      |
| 32                     | Cleaning $2\frac{1}{2}$ " cast iron pipe ...                                                                                                                                    | R.ft.   | 1,590    |
| 33                     | Laying and jointing $2\frac{1}{2}$ " cast iron pipe ...                                                                                                                         | Cwt.    | 155      |
| 34                     | Do 3" do ...                                                                                                                                                                    | "       | 315      |
| 35                     | Do 3" lead joints ...                                                                                                                                                           | No.     | 48       |
| 36                     | Do 3" cement joints ...                                                                                                                                                         | "       | 257      |
| 37                     | Do $2\frac{1}{2}$ " lead joints ...                                                                                                                                             | "       | 30       |
| 38                     | Do $2\frac{1}{2}$ " cement joints ...                                                                                                                                           | "       | 160      |
| 39                     | Do 3" cast iron cuts ...                                                                                                                                                        | "       | 8        |
| 40                     | Do $2\frac{1}{2}$ " cast iron cuts ...                                                                                                                                          | "       | 10       |
| 41                     | Do 2" galvanized cuts ...                                                                                                                                                       | "       | 2        |
| 42                     | Fixing sluice valves with rubber insertion, etc., complete ...                                                                                                                  | "       | 2        |
| 43                     | Fixing cast iron branch ...                                                                                                                                                     | "       | 2        |
| 44                     | Unloading 3" cast iron pipes from Railway waggon ...                                                                                                                            | Cwt.    | 315      |
| 45                     | Loading above to carts ...                                                                                                                                                      | "       | 315      |
| 46                     | Carting 3" cast iron pipes from Railway Station to work site average lead being $1\frac{1}{2}$ miles.                                                                           | "       | 315      |
| 47                     | Conveying $2\frac{1}{2}$ " cast iron pipes on the lines ...                                                                                                                     | "       | 155      |
| 48                     | Constructing masonry cistern for stop valves ...                                                                                                                                | No.     | 2        |
| 49                     | Constructing cisterns for gland locks ...                                                                                                                                       | "       | 1        |
| 50                     | Linking existing house connections to new main ...                                                                                                                              | Lumpsum | Rs.      |

B. R. GARUDACHAR,  
*Executive Engineer.*

GOVERNMENT OF MYSORE, STORES PURCHASE COMMITTEE, BANGALORE

No S. P. C. 6146-70, dated 12th November 1929.

To

The Firms dealing in hardware.

Gentlemen,

*Galvanised Iron Piping and other materials.*

Please quote your best prices for the materials described below delivered at Chikmagalur or in the alternative F. O. R. Birur, and state also if they can be delivered from immediate stocks in case an order is placed with you for the same. Your quotation should reach the undersigned by the 18th instant at the latest:—

5,000 feet  $3/4$  inch galvanised Iron Piping, with necessary collars.

24 T.-pieces  $3/4$  inch diameter.

12 Elbows  $3/4$  inch diameter.

6  $3/4$  inch taps with arrangements for locking the taps.

6 Miller Locks.

16  $3/4$  inch unions.

3 Wheel valves (steam tested).

Yours faithfully,

E. V. GANAPATHI IYER,

Secretary, Stores Purchase Committee.